

NEW ENGLAND DISTRICT MITIGATION GUIDANCE

for NEW ENGLAND DISTRICT MITIGATION PLAN CHECKLIST

TABLE OF CONTENTS

Introduction

- A. General Information
- B. Impact Area(s)
- C. Mitigation Area(s)
- D. Hydrology
- E. Grading Plan
- F. Topsoil
- G. Planting Plan
- H. Coarse Woody Debris and Other Features
- I. Erosion Controls
- J. Invasive and Noxious Species
- K. Off-Road Vehicle Use
- L. Preservation
- M. Monitoring Plan
- N. Assessment Plan
- O. Contingency
- P Long Term Stewardship
- Q. Other Comments

INTRODUCTION

Applicants should contact the Corps prior to initiation of site selection and mitigation plan development because mitigation requirements are project-specific. This New England District document and the associated New England District Mitigation Plan Checklist ("Checklist") are for use when the Corps determines mitigation is appropriate for a particular project. They represent New England District policy and have already incorporated the requirements of the following documents:

- 1. Model Compensatory Mitigation Plan Checklist and supporting supplement (http://www.mitigationactionplan.gov/checklist.pdf) and
- 2. Incorporating the National Research Council's Mitigation Guidelines into the Clean Water Act Section 404 Program.

 (http://www.mitigationactionplan.gov/nas404program.pdf)
- 3. Regulatory Guidance Letter 06-03: Minimum Monitoring Requirements for Compensatory Mitigation Projects Involving the Creation, Restoration, and/or

Enhancement of Aquatic Resources (http://www.usace.army.mil/cw/cecwo/reg/rgls/rgl06_03.pdf)

In addition, federal agencies involved with mitigation are developing guidance on many aspects of mitigation. The status of the Mitigation Action Plan components, and the guidance documents themselves as they are completed, is available at http://www.mitigationactionplan.gov/.

The purpose of this document is twofold:

- 1. To provide guidance to the regulated community on the requirements for mitigation required by the Corps of Engineers, New England District, and
- 2. To provide a standardized format for the Corps to use in reviewing mitigation plans for their technical merit.

It is important to note that there is some flexibility in the document. For example, it is not designed to be specific to tidal wetland creations and would therefore need to be modified for such situations. When variances are necessary, the proposed mitigation plan should provide a simple explanation of the rationale. However, some items are required by law or policy and are indicated by use of the term "must." We acknowledge that absolutes are rare in mitigation design and that a successful site requires careful design, detailed review, and common sense oversight during construction by a person well versed in wetland science.

All checklist items should be included in the mitigation plan or there should be an explanation as to why they are not appropriate.

After Corps review, items <u>not</u> marked with OK, N/A (Not Applicable), or NONE should be addressed by the applicant. A sample table format to cross-reference the checklist and a mitigation plan is included as Table 1.

Occasionally there are conflicts between requirements of the Corps and those of state and/or local agencies. Notify the Corps when this situation arises and the Corps will work with the applicant and state or local agencies to avoid duplication of effort and meet agency requirements. Normally, use of the most rigorous standard will be acceptable to all agencies. Note that the Corps prefers to receive only one monitoring report per project per year.

The used throughout this document indicates text which should typically be included in the mitigation plan.

Definitions

These definitions are for use with this document. Somewhat different definitions may exist in other documents.

<u>Mitigation in relation to S.404</u>: While mitigation includes sequencing from avoidance to minimization to, finally, compensation, it is frequently used instead of "compensation," including in this document.

<u>Compensatory mitigation</u>: Action taken which provides some form of substitute aquatic resource for the impacted aquatic resource. It may include created, restored, enhanced wetlands, streams, mudflats, etc. and preserved wetlands, streams, and/or uplands.

<u>Wetlands creation</u>: The transformation of upland or deepwater habitat to wetland at a site where the upland or deepwater habitat was not created by human activity. It is sometimes referred to as "establishment." Wetlands creation results in a gain in wetland acreage.

<u>Wetlands restoration</u>: Returning a former wetland area, which had been filled, drained, or excavated so that it no longer qualifies as a wetland, to wetland conditions. It is sometimes referred to as "re-establishment." Wetlands restoration results in a gain in wetland acreage.

<u>Wetlands enhancement</u>: Restoring degraded FUNCTIONS of an existing wetland. Degradation may result from infestation by invasive species, partial filling that does not create upland, deliberate removal of woody species (natural changes such as flooding and subsequent demise of trees as a result of beaver activity is not degradation), partial draining, etc. Restoration of an existing wetland's natural functions is sometimes called "rehabilitation." Wetlands enhancement does <u>not</u> result in a gain in wetland acreage.

<u>Invasive species</u>: Native and non-native species which aggressively move into areas, especially those that are disturbed, and crowd out less aggressive native species.

<u>Noxious weed</u>: Any living stage, such as seeds and reproductive parts, of any parasitic or other plant of a kind, which is of foreign origin, is new to or not widely prevalent in the United States, and can directly or indirectly injure crops, other useful plants, livestock, or poultry or other interests of agriculture, including irrigation, or navigation, or the fish or wildlife resources of the United States or the public health.¹

<u>Exotic species</u>: Species not native to New England, and usually not native to North America.

<u>Cultivars:</u> Non-native species or varieties which are developed for cultivation (e.g., agriculture, landscaping).

¹ From the 1974 Federal Noxious Weed Act

<u>Wetland scientist</u>: The applicant should work with the Corps Project Manager to determine the appropriate expertise for the "wetland scientist" needed to oversee a particular project.

Data Presentation

The use of charts, tables, and plan overlays to present data for impact and mitigation areas is encouraged. They are often the most concise method of conveying information and make comparison easier. Tables 2 and 3 at the end of this Introduction are examples of useful presentations of data.

<u>Temporal Losses</u>

All projects which do not have advance mitigation will result in temporal losses which occur as a result of the passage of time between the time when wetland functions are lost to the project impact and when they exist to a similar degree in a compensatory wetland. For example, the wildlife and ecosystem support functions of forested wetlands may take 30-50 years or more to develop. Applicants should be aware that additional compensation is likely to be required to offset temporal losses. Functions which *may* not lag behind mitigation construction are flood storage and groundwater discharge and/or recharge. While sediment trapping may develop relatively quickly, water quality functions can take many years to develop as they depend upon the chemical and biological characteristics of the wetland soils. The amount of additional compensation will depend upon the nature of the wetland proposed and the functions intended. Such compensation may include increased area for wetland creation, restoration, or enhancement or it may be solely additional preservation.

Effective Replacement of Functions

In addition, applicants should expect that more than 1:1 acreage replacement will usually be deemed appropriate BASED ON WETLAND FUNCTIONS impacted and likely to be established, temporal loss of functions, and a "safety factor". The baseline addresses the expected reduction in function (wildlife habitat, water quality functions performed by soils, etc.) of created or restored wetlands in comparison with wetlands formed in place. It also includes a safety factor to allow for some degree of failure. It has been our experience that some portion of most mitigation sites fail to establish wetland conditions or fail to develop the appropriate hydrology which affects resulting wetland functions.

Wetland mitigation is not an exact science; an adaptive management attitude is a necessity. Consider incorporating experimentation such as including experimental plots with different controls and treatments. This approach requires detailed planning, effective implementation of the plan, close monitoring, adjusting to intermediate results, and making additional modifications when needed to reach the long-term goals.

Checklist

Many items on the checklist are self-explanatory. Those which require specific guidance or clarification are noted below.

A. GENERAL INFORMATION

- 1. To avoid confusion, all mitigation proposal materials should be submitted as a single package without extraneous information that is needed for the permit evaluation but is not pertinent to the mitigation itself.
- **2. a.** Locus maps that show the location of the impact area and the location of mitigation sites including preservation areas are critical components of the plan. They should depict the geographic relationship between the impacted site(s) and the proposed mitigation site(s) and include a vicinity map of approximately 1 inch equals 2,000 feet. For sites where the relationship between the impacted site(s) and proposed mitigation site(s) is not clear at USGS quadrangle scale, an additional plan should be provided at an appropriate scale.
- **b.** Aerial photographs, if available, should be included. There are several on-line sources available. Recent photographs are preferred.
- **c.** Longitude and latitude of the mitigation site(s), including preservation areas, should be given in decimal format, rather than degrees and minutes or UTMs.
- **d.** Watershed(s) must be identified using the USGS 8-digit Hydrologic Unit Code(s) for each mitigation site (See Item A.2 on the Checklist), including preservation sites. One source of these codes is an EPA website at: http://cfpub.epa.gov/surf/locate/index.cfm.

B. IMPACT AREA(S)

Impact areas include both wetlands and waters. Most of the checklist items are self-explanatory but clarification is provided for stream information, functions and values assessment, and watershed plans.

2. Wetlands at each impact site should be described using Cowardin, et. al.² **and** hydrogeomorphic³ classification systems.

² Cowardin, et. al. (1979) "Classification of wetlands and deepwater habitats of the United States," Office of Biological Services, FWS/OBS-79/31, December 1979.

³ Brinson, M. M. (1993). "A hydrogeomorphic classification for wetlands," <u>Technical Report WRP-DE-4</u> http://www.wes.army.mil/el/wetlands/pdfs/wrpde4.pdf, U.S. Army Engineer Waterways Experiment Station, Vicksburg, MS. NTIS No. AD A270 053.

- **3.** If any streams will be impacted, information needed includes length of banks to be impacted, nature of banks, normal seasonal flows, gradient, sinuosity, bed load, lengths of riffles and pools, and adjacent landscape. Note that Regulatory Guidance Letter 02-2 states that stream functions lost must also be mitigated.
- **4.** When performing functions and values assessments, simply stating "wildlife habitat" or "fishery habitat" is inadequate. Additional information needs to be provided. Provide indicator species for the habitat type such as forest-dwelling migratory birds or mole salamanders and/or woodfrogs for a vernal pool. The more specific the information, the more confidence the Corps will have in the evaluation.
- **6.** Watershed and/or regional plans that describe aquatic resource objectives should be discussed if such plans are available for the impact area(s). If no such plans exist, this should be stated.

C. MITIGATION AREA(S)

- **1.** Background Information
- **a.** Provide an explanation of sites and methodologies considered for mitigation activities and the rationale for selection or rejection. Attachments 1 and 2 discuss when use of a potential mitigation site is practicable, whether on-site or off-site mitigation is appropriate, and whether out-of-kind mitigation is appropriate instead of in-kind. In order to replace the impacted functions, in-kind mitigation is strongly preferred unless the impacted site is heavily degraded.

Long-term sustainability is a key feature of successful wetland mitigation. Wherever possible, select sites where wetlands previously existed and/or where nearby wetlands currently exist. Restoration is frequently more feasible and sustainable than creation of wetlands.

Also, whenever possible, locate the mitigation site in a setting of comparable landscape position and hydrogeomorphic class as the impact wetland.

b. - e. Information on the selected site(s)'s existing wildlife usage, soils, vegetation, and surrounding land use are required. **Wildlife usage** must include information on any probable state and federal threatened and endangered species habitat. Subsurface **soil conditions** have a critical role in mitigation design, whether the substrate is sand, loam, silt, clay, and/or bedrock. Therefore, soil profiles should be provided that extend down to at least two feet below the proposed new soil surface. Since much of New England has been and continues to be heavily developed, there is a potential for industrial and agricultural contaminants in the soil. Although contamination does not necessarily preclude the use of a site, testing that is commensurate with the risk may be needed. Describe the existing **vegetation** on the site including a list of species, dominant species, density, community types,

and community structure. **Surrounding land use** should be described within at least 500 feet of the site(s) and include a discussion of likely <u>future</u> land uses. Include a discussion of how the site(s) plans fit into the watershed context and the proximity of the site to public and private protected lands.


- **f.** USFWS and/or NOAA Clearance Letter or Biological Opinion is to ensure that threatened or endangered species will not be impacted by the mitigation. This is not necessarily addressed in those agencies' comments on the proposed project requiring mitigation.
- **g.** SHPO/THPO letters on the proposed project also may not address potential concerns at the mitigation site.
- **2.** Mitigation Proposed
- **a. c.** Similar information is required for the mitigation area(s) as for the impacted area(s). Along with mitigation acreage at each site, the type of mitigation (i.e., creation, restoration, enhancement, preservation) should be identified. A single mitigation site may not be able to provide the full range of functions desired because some functions are incompatible. For example, some wildlife habitat may not be compatible with flood storage.

Typically, detention/retention basins are not acceptable for use as compensatory mitigation. Their construction results from requirements of the constructed project to mitigate stormwater concerns for the project itself, not address the lost functions of the impacted wetlands. In addition, they often require frequent maintenance to retain functionality, decreasing their ability to develop a full suite of wetland functions. However, detention/retention basins can serve to minimize the adverse effects of a project on nearby wetlands and waters, provided that the stormwater management system will be maintained for the life of the project.

- **d.** In general this should be on a 1:1 linear foot of bank basis unless a functional assessment methodology indicates that another basis for mitigation is appropriate. Again, Regulatory Guidance Letter 02-2 states that stream functions lost must also be mitigated.
- **f.** Frequently mitigation designs are constrained by the project itself, landscape features, or public issues that control or otherwise influence the design and/or monitoring and remediation of the mitigation area. Such constraints need to be explained in detail. If there are no constraints (rare), that should be stated in the plan.
- **g.** To ensure that someone with expertise in wetland science provides construction oversight for the mitigation project, the following language should be included in the narrative portion of the mitigation plan:

A wetland scientist shall be on-site to monitor construction of the wetland mitigation area(s) to ensure compliance with the mitigation plan and to make adjustments when appropriate to meet mitigation goals.


h. Construction timing of the mitigation and the proposed wetland impacts affects temporal impacts. Therefore, the following language should be included in the narrative portion of the mitigation plan:



If the impact will occur before the mitigation is constructed, the mitigation plan will address temporal losses.

In either of the above situations, the permittee will work with the Corps to develop financial assurances for the mitigation construction and monitoring, including remedial actions.

- **i.** All parties legally responsible for planning, accomplishing, and maintaining the mitigation project are identified.
- **j.** In accordance with national guidance, financial assurances will be required when the Corps determines it is appropriate to ensure successful implementation of the mitigation⁴. This will include most projects where the mitigation work is not accomplished in its entirety prior to the permitted impacts to aquatic resources. The text to use when such assurances are required is:



⁴ State Departments of Transportation are excluded from this type of financial assurance requirement.

Upon completion of construction and written concurrence from the Corps, the bond may be reduced to an amount that will cover the costs of monitoring and possible remedial actions.

Note that other forms of acceptable security may be possible such as postal money order, certified check, cashier's check, irrevocable letter of credit, or, in accordance with Treasury Department regulations, certain bonds or notes of the United States. However, please discuss alternatives to performance bonds with the Corps prior to their use.

Treasury Department Circular 570 is published in the Federal Register, and may be obtained from the U.S. Department of Treasury, Financial Management Service, Surety Bond Branch, 401 14th Street, NW, 2nd Floor, West Wing, Washington, DC 20227, or found at http://www.fms.treas.gov/c570/index.html.

k. Wildlife can pose serious threats to aircraft and therefore mitigation sites near airports are of concern to the Federal Aviation Administration. See Federal Aviation Administration Advisory Circular AC No: 150/5200-33, 5/1/97, http://www1.faa.gov/arp/pdf/5200-33.pdf.

D. HYDROLOGY

Avoid use of water-control structures which must be maintained in perpetuity.

1. The expected seasonal depth, duration, and timing of both inundation and saturation should be described for each of the proposed habitat zones in the mitigation area (particularly related to root zone of the proposed plantings). If shallow monitoring wells are used to develop this rationale, the observations should be correlated to local soil morphologies, rooting depths, water marks or other local evidence of flooding, ponding, or saturation, and reflect rainfall conditions during monitoring.

Monitoring Wells

Note that monitoring wells may not be necessary if other data are adequate. Please discuss this issue with Corps staff prior to installation.

Many mitigation plans include monitoring well data. Note that there is an important difference between monitoring wells and piezometers, both of which provide useful information. Since accurate placement and installation of monitoring wells and/or piezometers affects the accuracy and usefulness of the data, details on the uses for and installation of both of these types of wells are available in two documents prepared by the Engineers Research and Development Center's Environmental Lab, previously known as the Waterways Experiment Station:

- "Installing Monitoring Wells/Piezometers in Wetlands", ERDC TN-WRAP-00-02, can be found at: http://el.erdc.usace.army.mil/wrap/pdf/tnwrap00-2.pdf,
- "Technical Standard for Water-Table Monitoring of Potential Wetland Sites", ERDC TN-WRAP-05-02, can be found at: http://el.erdc.usace.army.mil/wrap/pdf/tnwrap05-2.pdf.

If monitoring wells are used and the site is adjacent to a wetland system, installation of at least one well in the adjacent system may provide useful information on the relationship of the water table in the wetland to the one in the proposed mitigation site.

2. Plan indicates if the water source is groundwater, surface runoff, precipitation, lake and/or stream overflow, tidal, and/or springs and seeps. Provide substantiation (e.g., well data, adjacent wetland conditions, stream gauge data, precipitation data). Precipitation data is available on the Internet. Sites include http://www.erh.noaa.gov under the appropriate Eastern Region Weather Forecast Office and the Northeast Regional Climate Center (http://www.nrcc.cornell.edu).

If stormwater from the project is part of the water budget, information should be provided if that water contribution will not be immediately available. For example, in a highway project, if the mitigation grading will be completed before the highway but the portion of the runoff intended to flow to the mitigation will not be directed to the site immediately, this should be explained. This does not imply that a detention basin will be considered compensatory mitigation nor does it imply that mitigation close to an impact area will be appropriate to compensate for all the impacted functions.

3. If vernal pool creation is included as part of the mitigation plan, provide evidence that adequate hydrology will be provided to support the target obligate vernal pool species (mole salamanders, woodfrogs, and/or fairy shrimp).

E. GRADING PLANS

- **1. a.** Plan provides existing and proposed grading plans for mitigation area. Existing contours should be to at least 2' intervals. Proposed contours should be to 1' intervals in the wetlands portion of the mitigation with spot elevations for intermediate elevations. All other areas should be shown at 2' contour intervals.
- b. Where microtopographic variation is planned, the proposed maximum differences in elevation should be specified. The plan does not need to show the locations of each pit and mound as long as a typical cross-section and approximate number of pits and mounds is given for each zone. Note that natural wetland systems with trees and/or shrubs typically have microrelief so created or restored areas of those types should typically have similar variability.

d. Plans should be on $8 \frac{1}{2} \times 11$ " sheets. Large size sheets are encouraged for clarity, but only as a supplement to the letter-sized sheets.

Soil compaction by heavy machinery may adversely affect plantings and/or may result in perching of water. Therefore, efforts should be made to minimize soil compaction area during grading of the mitigation site. If use of heavy machinery cannot by avoided, compaction must be addressed by disking or some other treatment to loosen the soil surface. Similar consideration should be given while spreading the topsoil.

- **f.** The drawings should show the access for maintenance and monitoring.
- **2.** Plan provides representative cross sections showing the existing and proposed grading plan, expected range of shallow groundwater table elevations or surface water level consistently expected. Cross-sections should include key features such as upland islands and pools. They should extend beyond the mitigation site into adjacent wetlands and uplands.

F. TOPSOIL

Manmade topsoil shall consist of a mixture of equal volumes of organic and mineral materials. Well-decomposed clean leaf compost is the preferred soil amendment to achieve these standards. Note that "clean" refers both to the lack of physical contaminants such as plastic and to the lack of chemical contaminants. If other soil amendments are more readily available than clean leaf compost they can be used to meet the requirement for the appropriate percent organic carbon content (see Item F.3). Note, however, that compost or other organic matter should be clean and free of weed seeds, specifically the seeds of the species listed in Table 4. Peat is not recommended for soil amendments as its harvesting methods are generally destructive to wetlands.

It is important to keep in mind the difference between organic *matter* and organic *carbon* both for meeting regulatory guidelines and when classifying the surface horizons in soils as histic (organic soils), mucky modified or mineral. The organic *carbon* content of most upland topsoil is between 1 and 6 percent of dry weight. Soils with more than 20 to 30 percent organic *matter* (12 to 17 percent organic *carbon* content) are known as organic soils or Histosols. The Field Indicators for Identifying Hydric Soils in New England (New England Hydric Soils Technical Committee, 2004, 3rd ed.) glossary defines the criteria for these classifications based on their organic *carbon* contents. 4-12% minimum organic *carbon* content (9 to 21 percent organic *matter*) on a dry weight basis for soils should be used in wetland replication areas. The rule of thumb for conversion is to divide organic *matter* by

1.72 to get organic *carbon* content and multiply organic *carbon* by 1.72 to get organic *matter* content⁵:

$$O_{\rm m}/1.72 = O_{\rm c}$$
 and $O_{\rm c} \times 1.72 = O_{\rm m}$

Scrub-shrub and forested wetlands should have about 12% organic carbon; emergent wetlands in permanently or semi-permanently inundated areas may only need 4-6%.

Note that the term "loam" that is frequently used for the material spread on a mitigation site after subsoil grading is a landscaping term. In soil science, the term refers to a specific texture of soil comprised of specific amounts of sand, silt, and clay particles. The landscaping term is not a scientific term and should be avoided.

When topsoil must be stockpiled on site, the plan should include plans for maintaining moisture in the soil. The following measures are suggested for the contractor doing the work:

- Seek approval for location of stockpiled materials (from owner/engineer);
- Avoid stockpiling compost organics in piles over 4 feet in height;
- Protect stockpiles from surface water flow and contain them with haybales and/or siltfence;
- Cover stockpiles with a material that prevents erosion (tarps, erosion control mat, straw and temporary seed, depending on size and duration of storage)
- Inspect and repair protection measures listed above regularly (weekly), as well as prior to (to the extent possible) and after storm events.
- Maintain moisture in the soils during droughty periods.
- **1.** Topsoil for mitigation sites can be a source of invasive species seeds. Provide information on the source and the likelihood that such seeds are in it.
- **2.** Twelve or more inches of natural or manmade topsoil should be used in most wetland mitigation areas. Exceptions might be permanently or semi-permanently inundated or saturated areas and turtle nesting areas. Rationale for less than 12 inches should be provided.
- **3.** Natural topsoil proposed to be used for the creation/restoration/ enhancement of wetlands consists of at least 4-12% organic carbon content (by weight) (or 9-21% organic matter content), **with the percentage specified**. Manmade topsoil used for the creation/restoration/enhancement of wetlands consists of a mixture of equal volumes of organic and mineral materials. This may be accomplished by adding a specific depth of organic material and disking it in to twice that depth. The actual

⁵ Excerpted from Allen, Art, "Organic Matters", *AMWS Newsletter*, December 2001.

measured organic content of the topsoil used should be provided in the as-built plan submitted with the first monitoring report.

G. PLANTING PLAN

Planting and/or seeding are generally appropriate for a mitigation site, as determined through consultation with the Corps. When planting is proposed as part of the plan, the guidelines noted below should be followed.

<u>Irrigation</u>

Note that irrigation is solely to enhance the success of vegetation establishment, not to provide hydrology. The use of irrigation for woody plantings should be considered for the first one to two growing seasons after planting due to the unpredictability of short-term local hydrologic conditions and the need for additional care to establish new plantings. Equipment (e.g., pipes, pumps, sprinklers) must be removed and irrigation discontinued no later than the end of the second growing season unless the Corps concurs with extended irrigation. In this situation, the monitoring period shall be extended an equivalent time period.

Two methods have been used successfully: water trucks and installation of irrigation systems. The former is limited by accessibility for the truck(s), a likely problem on large sites. The latter tends to be less expensive and may be more effective for large projects.

Use of Mulch

The use of mulch around woody plantings is strongly encouraged, and may be required, to reduce the need for irrigation and to keep down herbaceous vegetation in the immediate vicinity of each plant for a couple of years. There are at least two methods available: biodegradable plastic (which should be stapled to the ground) or organic mulch. Note that organic mulch should not be considered part of the organic content of the topsoil and it should not be used in locations that will be inundated as it may float away. Suggested specifications for organic mulching are as follows:

- Mulch balled and burlaped or container-grown trees and shrubs in a 3' diameter circle approximately 2" deep.
- Mulch bare-root woody planting in an 18" diameter circle approximately 2" deep.
- **1.** The use of scientific names ensures that all involved have the correct understanding of the species of plants proposed to be planted or seeded.

2. Native planting stock from the immediate vicinity of the project is ideal. Whenever possible, plants should be salvaged from wetlands and uplands cleared by the project. Transplanting entire blocks of vegetation with several inches of the original wetland soil substrate from the impact areas has been found very effective in establishing mitigation wetlands. However, beware of the potential for transplanting invasive species.

No cultivars shall be used. Beware of stock identified as a native species which is actually a cultivar or non-native species (e.g., there have been several instances around New England of *Alnus incana* or *Alnus rugosa* labels on non-native *Alnus qlutinosa*)

During the first few years while the designed wetland vegetative zones become established, they are susceptible to colonization and subsequent domination by invasive species. A number of plants are known to be especially troublesome in this regard. The following stipulation shall be included in the mitigation plan, either in the plan view or in the narrative portion of the plan:

- To reduce the immediate threat and minimize the long-term potential of degradation, the species included on the "Invasive and Other Unacceptable Plant Species" list in Table 4 of the New England District Mitigation Plan Guidance shall not be included as planting stock in the overall project. Only plant materials native and indigenous to the region shall be used (with the exception of **[specify]**). Species not specified in the mitigation plan shall not be used without prior written approval from the Corps.
- **3.** The Cowardin (1979) classification system is typically used to identify the plant communities proposed. If another system is used, an explanation of terms may be needed.
- **4.** A plan view drawing should show where the various species are proposed to be planted. Since showing each individual plant is neither practical nor realistic, this may be illustrated with areas of uniform species composition and the number of plants or rate of seeding within the polygon. The scale should be in the range of 1"=20' to 1"=100', depending on the size of the site.
- **5.** Although the prevailing hydrology will ultimately influence the type of wetland that will develop, plantings "jump start" the project. Some species tend to volunteer promptly whereas others may take years to move into a site; consideration should be given to emphasize planting species unlikely to "volunteer" during the monitoring period.
- **6.** Woody stock should be proposed to be planted in densities not less than 600 trees and shrubs per acre, including at least 400 trees per acre in forested cover types.


Woody planting densities may require adjustment depending upon the goals of the mitigation plan and the 'reference wetland' used to develop the habitat goals. For example, if the primary goal for a particular creation site is flood storage and there is minimal need for wildlife habitat but there is interest in developing a woody component in the flood storage area, the density may be reduced. Also, if the wetland type desired is a dense thicket, the density may need to be increased.

- **7.** Where uniform coverage is anticipated, herbaceous stock should be proposed to be planted in densities not less than the equivalent of 3 feet on center for species which spread with underground rhizomes; 2 feet on center for species which form clumps.
- **8.** The list of species proposed in seed mixes should not include any species in the list of invasives in Table 4. Similarly, non-native genotypes and cultivars should not be used.

Although the use of non-native species is typically discouraged, there are situations where such use may be appropriate such as using *Secale cereale* (Annual Rye) to quickly stabilize a site. The species should be noted and the reason for their use explained.

Species listed in Table 4 are not to be included as seed or planting stock in the overall project.⁶ Most of these species do not need to be actively removed from the site. Exceptions are included in the Monitoring section (Section M). More may be added by the Corps on a case-by-case basis.

- **9.** Cross-sectional drawings should include identification of vegetative community zones (e.g., forested, shrub swamp, etc.). This can be combined with the plans required for grading if they are not too complex.
- **10.** The following stipulation shall be included in the mitigation plan, either in the drawings or in the narrative portion of the plan:



1/12/2007

⁶ This list is a compilation of state lists from New England and additional species recommended by regional botanical experts.

H. COARSE WOODY DEBRIS AND OTHER FEATURES

Coarse woody debris includes such materials as logs, stumps, smaller branches, and standing snags. Placement of this material is generally inappropriate in tidal or frequently flooded environments, and may not be appropriate for herbaceous systems. As much as possible, these materials will be in various stages of decomposition and salvaged from natural areas cleared for the other elements of the project. The following language is included in the mitigation plan, either in the drawings or in the narrative portion of the plan:

A supply of dead and dying woody debris shall cover at least 4% of the ground throughout the mitigation sites after the completion of construction of the mitigation sites. These materials should not include species shown on the list of invasive species (Table 4) in the New England District Mitigation Plan Guidance.

When mitigation requires a component of forest or scrub-shrub habitat, the design should include plans for a continuum of coarse woody debris, including snags (standing dead trees).

When a tree dies, it may continue to provide habitat for another century or longer. The speed of the recycling processes depends on many factors, but the main point is that coarse woody materials are relatively durable and remain as important ecological features both below- and above-ground for a long time. Long after the last needles or leaves fall to the forest floor, a tree persists, parceling itself out in bits and pieces.

In the first years, if a tree remains upright, the greatest volume of its litter may consist of bark, twigs, and small branches. Later, as insects and fungus weaken the aerial framework, larger limbs and sections of the trunk tumble to the ground where decay occurs under quite different conditions. On the forest floor, well-decomposed logs may sustain greater faunal richness. In an ideal situation, there is an uninterrupted supply of woody litter in various sizes and stages of decay providing a diverse range of habitats. Decomposition is one of the natural processes in a healthy forest. If one link of the chain is lacking, the process falters. Wetland builders should factor coarse woody debris into most habitat mitigation strategies.

Frequently the inclusion of scattered various sized boulders, as well as woody debris is an appropriate method of increasing structure and habitat in a site. Note of caution: if not properly screened by a wetland scientist, such debris can be a source of invasive species.

I. EROSION CONTROLS

The following language is included in the mitigation plan, either in the drawings or in the narrative portion of the plan:

Temporary devices and structures to control erosion and sedimentation in and around mitigation sites shall be properly maintained at all times. The devices and structures shall be disassembled and properly disposed of as soon as the site is stable but no later than November 1 three full growing seasons after planting. Sediment collected by these devices will be removed and placed upland in a manner that prevents its erosion and transport to a waterway or wetland.

Cordoning off of an entire site with erosion controls is discouraged as it impedes animal movement. If circling of an entire site is needed, either gaps or overlaps with intervening space should be provided.

J. INVASIVE AND NOXIOUS SPECIES

Projects should avoid introducing or increasing the risk of invasion by unwanted plants (such as those listed in J.3. below) or animals (such as zebra mussels). Soils disturbed by projects are very susceptible to invasion by undesirable species. Be particularly alert to the risk of invasion on exposed mineral soils. Exposed mineral soils may result from excavation or filling. Noxious species often get a foothold along project drainage features where the dynamics of erosion and accretion prevail. Along saltmarshes, be especially alert to the project's influence on freshwater runoff. Frequently, *Phragmites australis* invasion is an unanticipated consequence of freshwater intrusion into the saltmarsh. Information from the Invasive Plants Atlas of New England is available at: http://nbii-nin.ciesin.columbia.edu/ipane/.

- 1. The discussion of risk should include an assessment of the potential for invasion of the wetland by the species listed in J.3 or other identified problematic species specific to this project or site.
- **2.** The plan should identify regulatory and ecological constraints that influence the design of any plan to control invasive plants and animals by biological, mechanical, or chemical measures. For example, if a state requires a permit for use of herbicide, this may constrain attempts to control an invasive plant species. If there are no constraints, this should be stated.
- 3. The plan should describe the strategy to control, or recognize and respond to, the degradation of the mitigation site by invasive or noxious plants. The plan should address a full range of practicable measures to minimize threats to wetlands as well as all associated buffers or other habitats that are factored in project impact mitigation by Common reed (*Phragmites australis*), Purple loosestrife (*Lythrum salicaria*), Buckthorns (*Rhamnus* spp.), Olives (*Elaeagnus* spp.), Multiflora rose (*Rosa multiflora*), Reed canary-grass (*Phalaris arundinacea*), Japanese knotweed (*Polygonum cuspidatum*), and any other species identified as a problem at the site. The plan should consider traditional control methods including: mechanical (pulling,

mowing, or excavating on-site), chemical (herbiciding), and biological (planting fast-growing trees and shrubs for shading or releasing herbivorous insects).

K. OFF-ROAD VEHICLE USE

If there is a potential for off-road vehicle access at the site, which may include snowmobile usage, the mitigation plan shall include a strategy to minimize impacts. Plans should illustrate locations of any necessary barriers placed at access points to the mitigation sites to prevent vehicles from damaging the sites.

L. PRESERVATION

1. Adequate buffers must be proposed to protect the ecological integrity of creation, restoration, and/or enhancement areas.

In most cases, a protected (preserved) buffer will be required around creation, restoration, and enhancement sites, including stream mitigation as this is of benefit on a local and watershed scale throughout New England. The extent of the buffer will depend upon the landscape position of the site(s) and current and potential surrounding land uses but it will be rare that a buffer less than 100 feet in width will be adequate. Usually buffers will consist of uplands but wetlands also may serve that function.

- **2.** Wetlands within subdivisions, golf courses, etc. should generally be protected along with appropriate buffers. This is part of the avoidance and minimization steps of mitigation, not part of compensation.
- **3.** Preservation should be part of every mitigation package as preservation of a creation, restoration, or enhancement area, and buffer; the remaining unimpacted wetlands on-site as part of avoidance and minimization; as a stand-alone form of mitigation; or as any combination of these. Ideally the preservation document will be prepared, reviewed, and approved by the Corps prior to submission of the final mitigation plan and permit issuance. If this is not possible, the following language should be included in the plan⁷:

-	Compensatory mitigation sites and on-site unimpacted wetlands (and buffers)
	to be set aside for conservation shall be protected in perpetuity from future
	development. Within 90 days of the date this permit is issued and prior to
	initiation of permitted work in aquatic resources, the permittee shall submit to
	the Corps of Engineers a draft of the conservation easement or deed
	restriction. Within 30 days of the date the Corps approves this draft document
	in writing, the permittee shall execute and record it with the Registry of Deeds
	for the Town of and the State of A copy of the executed

⁷ Departments of Transportation, in particular, may need to have the timing requirements modified. This will be addressed on a case-by-case basis.

and recorded document must then be sent to the Corps of Engineers within 90 days of the date it was recorded. The conservation easement or deed restriction shall enable the site or sites to be protected in perpetuity from any future development. For preservation as part of compensation, the conservation easement or deed restriction shall expressly allow for the creation, restoration, remediation and monitoring activities required by this permit on the site or sites. It shall prohibit all other filling, clearing and other disturbances (including vehicle access) on these sites except for activities explicitly authorized by the Corps of Engineers in these approved documents.

If it is possible to have the document prepared and approved prior to final mitigation plan submission and permit issuance, only the following needs to be included:

\rightarrow	Within 30 days of the date of permit issuance and prior to initiation of
	permitted work in aquatic resources, the permittee shall execute and record
	the preservation document with the Registry of Deeds for the Town of -
	and the State of A copy of the executed and recorded
	document must then be sent to the Corps of Engineers within 90 days of the
	1 0
	date it was recorded.

- **4.** Plans showing the location of all sites to be preserved are required. In addition to a locus, they must be sufficiently detailed to determine relationships to adjacent development and/or properties as these adjacent areas affect the long term sustainability of the site. In some cases it may be appropriate to have signs at the boundaries of the preservation area(s). The sign design should be noted in the documentation.
- **5.** There are numerous forms of preservation documents. They include fee transfer to another entity such as a non-profit organization or public agency, easement given to a non-profit organization or public agency, deed restriction, or restrictive covenant. The form should be specified or a copy of the document(s) included. Fee transfer and conservation easements are preferred. Deed restrictions are discouraged as they are difficult to enforce and are often easily changed.

M. MONITORING PLAN

Once the final mitigation plan is incorporated into the permit, the permit will require full implementation of the mitigation plan, including remedial measures during the first five or more growing seasons to ensure success. Typically, sites proposed to be emergent-only wetlands will be monitored for five years and sites proposed to be scrub-shrub and/or forested wetlands will be monitored for five to ten years (years 1, 2, 3, 5, 7, and 10 for the latter), as extended periods for monitoring will be appropriate in some cases. Failure to implement the plan and remedial measures constitutes permit non-compliance as do failure to submit copies of financial assurances and/or preservation documents and failure to submit required monitoring and assessment documents.

Electronic submission of monitoring reports is strongly encouraged. Portable Document Format is preferred (e.g., Adobe PDF). When submitted in electronic format, there is no restriction for using standard paper sizes. These monitoring reports should be concise and effectively provide the information necessary to assess the status of the compensatory mitigation project. Large, bulky reports containing general information are discouraged. The reports should follow a 10-page maximum report format per site, with a self-certification form transmittal. The information required below should be framed within this format.

1) Project Overview⁸ (1 page)

2) Requirements (1 page)

List the monitoring requirements and performance and/or success standards, as specified in the approved mitigation plan and special conditions of the permit, and evaluate whether the compensatory mitigation project site is successfully achieving the approved performance and/or success standards or trending toward success.

3) Summary Data (maximum of 4 pages)

Summary data must be provided to substantiate the success and/or potential challenges associated with the compensatory mitigation project. Photo documentation should be provided to support the findings and recommendations, and placed in the Appendix.

4) Maps (maximum of 3 pages)

Maps must be provided to show the location of the compensatory mitigation site relative to other landscape features, habitat types, locations of photographic reference points, transects, sampling data points, and/or other features pertinent to the mitigation plan. In addition, the submitted maps must clearly delineate the mitigation site boundaries to assist in proper locations for subsequent site visits. Each map or diagram must fit on a standard $8 \frac{1}{2} \times 11^{\circ}$ piece of paper and include a legend and the location of any photos submitted for review.

5) Conclusions (1 page)

A general statement must be included describing the conditions of the compensatory mitigation project. If performance or success standards are not being met, a brief discussion of the difficulties and potential remedial actions proposed by the permittee, including a timetable, must be provided.

⁸ see Attachment 1

The following language should be included in the narrative portion of the mitigation plan:



MONITORING

Notification of Construction Completion

Within 60 days of completing a mitigation project that includes restoration, creation, and/or enhancement, the applicant will submit a signed letter to the Corps, Policy Analysis and Technical Support Branch, specifying the date of completion of the mitigation work.

If mitigation construction is initiated in, or continues throughout the year, but is not completed by December 31 of any given year, the permittee will provide the Corps, Policy Analysis and Technical Support Branch, a letter providing the date mitigation work began and the work completed as of December 31. The letter will be sent no later than January 31 of the next year. The letter will include the Corps permit number.

Monitoring Report Guidance

For each of the first [specify] full growing seasons following construction of the mitigation site(s), the site(s) will be monitored and annual monitoring reports submitted. Observations will occur at least two times during the growing season in late spring/early summer and again in late summer/early fall. Each annual monitoring report will be submitted to the Corps, Regulatory Division, Policy Analysis and Technical Support Branch, no later than December 15 of the year being monitored. Failure to perform the monitoring and submit monitoring reports constitutes permit non-compliance. A self-certification form⁹ will be completed, and signed as the transmittal coversheet for each annual monitoring report and will indicate the permit number and the report number (Monitoring Report 1 of 5, for example). The reports will address the following successstandards in the summary data section and will address the additional items noted in the monitoring report requirements, in the appropriate section. The reports will also include the monitoring-report appendices listed below. The first year of monitoring will be the first year that the site has been through a full growing season after completion of construction and planting. For these special conditions, a growing season starts no later than May 31. However, if there are problems that need to be addressed and if the measures to correct them require prior approval from the Corps, the permittee will contact the Corps by phone (1-800-362-4367 in MA or 1-800-343-4789 in ME, VT, NH, CT, RI) or letter as soon as the need for corrective action is discovered.

See Attachment 2

Remedial measures will be implemented - at least two years prior to the completion of the monitoring period - to attain the success standards described below within **[specify]** growing seasons after completion of construction of the mitigation site(s). Should measures be required within two years of the end of the monitoring period, the monitoring period will be extended to ensure two years of monitoring after the remedial work is completed. Measures requiring earth movement or changes in hydrology will not be implemented without written approval from the Corps.

At least one reference site adjacent to or near each mitigation site will be described and shown on a locus map.

Success Standards

1) The site has the hydrology, as demonstrated with well data collected at least weekly from March through June or other substantial evidence, to support the designed wetland type.

Is the proposed hydrology met at the site? What percentage of the site is meeting projected hydrology levels? Areas that are too wet or too dry should be identified along with suggested corrective measures.

2) The proposed vegetation diversity and/or density goals for woody plants from the plan are met.

Unless otherwise specified in the mitigation plans, this should be at least 500 trees and shrubs per acre, of which at least 350 per acre are trees for proposed forested cover types, that are healthy and vigorous and are at least 18" tall in 75% of each planned woody zone AND at least the following number of non-exotic species including planted and volunteer species. Volunteer species should support functions consistent with the design goals. To count a species, it should be well represented on the site (e.g., at least 50 individuals of that species per acre).

# species planted	minimum # species required (volunteer and planted)
2	2
3	3
4	3
5	4
6	4
7	5
8	5

9 or more

6

Vegetative zones consist of areas proposed for various types of wetlands (shrub swamp, forested swamp, etc.). The performance standards for density can be assessed using either total inventory or quadrat sampling methods, depending upon the size and complexity of the site.

- 3) a. Each mitigation site has at least 80% areal cover, excluding <u>planned</u> open water areas or <u>planned</u> bare soil areas (such as for turtle nesting), by noninvasive species (See Table 4).
- b. Planned emergent areas on each mitigation site have at least 80% cover by noninvasive hydrophytes.
- c. Planned scrub-shrub and forested cover types have at least 60% cover by noninvasive hydrophytes, of which at least 15% are woody species.

For the purpose of this success standard, invasive species of hydrophytes are:

Cattails -- Typha latifolia, Typha angustifolia, Typha glauca; Common Reed -- Phragmites australis; Purple Loosestrife -- Lythrum salicaria; Reed Canary Grass -- Phalaris arundinacea; and Buckthorn - Rhamnus frangula.

4) Common reed (*Phragmites australis*), Purple loosestrife (*Lythrum salicaria*), Russian and Autumn olive (*Elaeagnus* spp.), Buckthorn (*Rhamnus* spp.), Japanese knotweed (*Polygonum cuspidatum*), and/or Multiflora rose (*Rosa multiflora*) plants at the mitigation site(s) are being controlled.

For this standard, small patches must be eliminated during the entire monitoring period. Large patches must be aggressively treated and the treatment documented.

5) All slopes, soils, substrates, and constructed features within and adjacent to the mitigation site(s) are stable.

Monitoring Report Requirements

Additional items for inclusion:

Project Overview

• Highlighted summary of problems which need immediate attention (e.g., problem with hydrology, severe invasives problem, serious erosion, major losses from herbivory, etc.). This should be at the beginning of the report and highlighted in the project overview and in the self-certification form.

Requirements

 A copy of this permit's mitigation special conditions and summary of the mitigation goals.

Summary Data

- Address success standards achievement and/or measures to attain the standards.
- Describe the monitoring inspections, and provide their dates, that occurred since the last report.
- Soils data, commensurate with the requirements of the soils portion of the 1987 Corps Wetlands Delineation Manual (Technical Report Y-87-1 and approved regional supplements) New England District data form, should be collected after construction and every alternate year throughout the monitoring period. If monitoring wells or gauges were installed as part of the project, this hydrology data should be submitted annually.
- Concisely describe remedial actions done during the monitoring year to meet the five success standards – actions such as removing debris, replanting, controlling invasive plant species (with biological, herbicidal, or mechanical methods), regrading the site, applying additional topsoil or soil amendments, adjusting site hydrology, etc. Also describe any other remedial actions done at each site.
- Report the status of all erosion control measures on the compensation site(s). Are they in place and functioning? If temporary measures are no longer needed, have they been removed?
- Give visual estimates of (1) percent vegetative cover for each mitigation site and (2) percent cover of the invasive species listed under Success Standard No. 3, above, in each mitigation site.
- What fish and wildlife use the site(s) and what do they use it for (nesting, feeding, shelter, etc.)?
- By species planted, describe the general health and vigor of the surviving plants, the prognosis for their future survival, and a diagnosis of the cause(s) of morbidity or mortality.

IF MITIGATION INCLUDES VERNAL POOL CREATION:

Does the vernal pool creation take into account the critical need for unobstructed access to and from the pool, as well as an adequate extent of upland habitat to ensure success?

Pool(s) are monitored for obligate and facultative vernal pool species weekly for four weeks from the beginning of the vernal pool activity in the spring (will vary throughout New England) and then biweekly until the end of July for the entire monitoring period. The period of monitoring is specified. Data identify frog species, salamander genera, and the presence/absence of fairy shrimp. Macroinvertebrates can be identified to the order.

In addition, photographs of the pool(s) taken monthly during the pool monitoring period (March/April-July) from a set location(s) will be included. Photographs will include panoramas of surrounding habitat.

Other data required: pH and temperature of water at beginning and end of each monitoring cycle; pool depth at deepest point(s) (or state if >3') to nearest inch or centimeter; substrate of pool(s) (dead leaves, herbaceous vegetation, bare soil—organic or mineral, etc.); plant species noted in and around the perimeter of the pool(s).

If the state has a vernal pool register or certification program, the pool(s) is registered and/or certified prior to the final monitoring report submission.

Conclusions

• What remedial measures are recommended to achieve or maintain achievement of the five success standards and otherwise improve the extent to which the mitigation site(s) replace the functions and values lost because of project impacts?

Monitoring Report Appendices

Appendix A -- An as-built plan showing topography to 1-foot contours, any inlet/outlet structures and the location and extent of the designed plant community types (e.g., shrub swamp). Within each community type the plan shall show the species planted—but it is not necessary to illustrate the precise location of each individual plant. There should also be a soil profile description and the actual measured organic content of the topsoil. This should be included in the first monitoring report unless there are grading or soil modifications or additional plantings of different species in subsequent years.

<u>Appendix B</u> – A vegetative species list of volunteers in each plant community type. The volunteer species list should, at a minimum, include those that cover at least 5% of their vegetative layer.

<u>Appendix C</u> -- Representative photos of each mitigation site taken from the same locations for each monitoring event. Photos should be dated and clearly labelled with the direction from which the photo was taken. The photo sites must also be identified on the appropriate maps.

N. ASSESSMENT PLAN

The following language should be included in the narrative portion of the mitigation plan:



ASSESSMENT

A post-construction assessment of the condition of the mitigation site(s) shall be performed following the fifth growing season after completion of the mitigation site(s) construction, or by the end of the monitoring period, whichever is later. "Growing season" in this context begins no later than May 31st. To ensure objectivity, the person(s) who prepared the annual monitoring reports shall not perform this assessment without written approval from the Corps. The assessment report shall be submitted to the Corps by December 15 of the year the assessment is conducted; this will coincide with the year of the final monitoring report, so it is acceptable to include both the final monitoring report and assessment in the same document.

The post-construction assessment shall include the four assessment appendices listed below and shall:

- Summarize the original or modified mitigation goals and discuss the level of attainment of these goals at each mitigation site (include vernal pool creation if that is a component of the mitigation).
- Describe significant problems and solutions during construction and maintenance (monitoring) of the mitigation site(s).
- Identify agency procedures or policies that encumbered implementation of the mitigation plan. Specifically note procedures or policies that contributed to less success or less effectiveness than anticipated in the mitigation plan.
- Recommend measures to improve the efficiency, reduce the cost, or improve the effectiveness of similar projects in the future.

ASSESSMENT APPENDICES:

<u>Appendix A</u> -- Summary of the results of a functions and values assessment of the mitigation site(s), using the same methodology used to determine the functions and values of the impacted wetlands.

Appendix B -- Calculation of the area of wetlands in each mitigation site using the 1987 Corps Wetlands Delineation Manual and approved regional supplements. Supporting documents shall include (1) a scaled drawing showing the wetland boundaries and representative transects and (2) datasheets for corresponding data points along each transect.

<u>Appendix C</u> -- Comparison of the area and extent of delineated constructed wetlands (from Appendix B) with the area and extent of created wetlands proposed in the mitigation plan. This comparison shall be made on a scaled drawing or as an overlay on the as-built plan. This plan shall also show the major vegetation community types.

<u>Appendix D</u> -- Photos of each mitigation site taken from the same locations as the monitoring photos, including photos of vernal pools, if applicable.

O. CONTINGENCY

Describe the procedures to be followed should unforeseen site conditions or circumstances prevent the site from developing as intended. Examples of such situations include unanticipated beaver activity, disruption of the groundwater by blasting or other construction in the vicinity, unexpected subgrade texture, unearthing an unexpected archaeological site, and encountering hazardous waste.

P. LONG TERM STEWARDSHIP

It is important that sites have long term sustainability and, as such, are protected from degradation. Applicants should consider both current and expected future hydrology (including effects of any proposed manipulations), sediment transport, locations of water resources, and overall watershed functional goals before choosing a mitigation site. This is extremely critical in watersheds that are rapidly urbanizing; changing infiltration rates can modify runoff profiles substantially, with associated changes in sediment transport, flooding frequency, and water quality. More importantly, applicants must plan for long-term survival by placing mitigation in areas that will remain as open space and not be severely impacted by clearly predictable development. Consideration of the landscape perspective requires evaluation of buffers and connectivity (both hydrologic- and habitat-related). Buffers are particularly important to insure that changing conditions are ameliorated, especially in watersheds that have been, or are in the process of being, heavily developed. In addition, because wetlands are so dynamic, adequate buffers and open space upland areas are vital to allowing for wetlands to "breath" (expand and/or

decrease in size and function) and migrate within the landscape, particularly in watersheds under natural and/or man-made pressures.

Appropriate provisions must be made to support the mitigation site in perpetuity. The owner of the site or the holder of a conservation easement will be responsible for ensuring the site is in compliance with the permit, including mitigation requirements, in perpetuity.

Q. OTHER COMMENTS

REFERENCES

Ashby, Steven. "Approaches for the Mitigation of Water Quality Functions of Impacted Wetlands – A Review," ERDC TN-WRAP-02-03 http://www.wes.army.mil/el/wrap/pdf/tnwrap02-3.pdf, U.S. Army Research and Development Center, Vicksburg, MS.

Brinson, M. M. (1993). "A hydrogeomorphic classification for wetlands," Technical Report WRP-DE-4. http://www.wes.army.mil/el/wetlands/pdfs/wrpde4.pdf, U.S. Army Engineer Waterways Experiment Station, Vicksburg, MS. NTIS No. AD A270 053.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T LaRoe. (1979) "Classification of wetlands and deepwater habitats of the United States," Office of Biological Services, FWS/OBS-79/31, December 1979.

Environmental Laboratory. (1987). "Corps of Engineers Wetlands Delineation Manual," Technical Report Y-87-1, http://www.wes.army.mil/el/wetlands/pdfs/wlman87.pdf, U.S. Army Engineer Waterways Experiment Station, Vicksburg, MS.

Federal Aviation Administration Advisory Circular AC No: 150/5200-33, 5/1/97, http://www1.faa.gov/arp/pdf/5200-33.pdf

Mehrhoff, L.J., J.A. Silander, Jr., S. A. Leicht and E. Mosher. 2003. IPANE: Invasive Plant Atlas of New England. Department of Ecology and Evolutionary Biology, University of Connecticut, Storrs, CT, USA. URL: http://invasives.eeb.uconn.edu/ipane/

Minkin, P. and R. Ladd. 2003. Success of Corps-Required Wetland Mitigation in New England. New England District Corps of Engineers, Concord, MA.

National Research Council. 2001. Compensating for Wetland Losses Under the Clean Water Act. National Academy Press. Washington, DC. 322 pp.

Sprecher, S. W. (2000). "Installing Monitoring Wells/Piezometers in Wetlands," <u>ERDC TN-WRAP-00-02 http://el.erdc.usace.army.mil/wrap/pdf/tnwrap00-2.pdf</u>, U.S. Army Research and Development Center, Vicksburg, MS.

Streever, W., and Perkins, E. (2000). "Importing plant stock for wetland restoration and creation: Maintaining genetic diversity and integrity," *WRAP Technical Notes Collection* (ERDC TN-WRAP-00-03), U.S. Army Engineer Research and Development Center, Vicksburg, MS. www.wes.army.mil/el/wrap

Treasury Department Circular 570.

- U.S. Army Corps of Engineers. 2002. Guidance on compensatory mitigation projects for aquatic resource impacts under the Corps Regulatory Program pursuant to Section 404 of the Clean Water Act and Section 10 of the Rivers and Harbors Act of 1899. Regulatory Guidance Letter No. 02-2.
- U.S. Army Corps of Engineers. 2005. "Technical Standard for Water-Table Monitoring of Potential Wetland Sites," *WRAP Technical Notes Collection* (ERDC TN-WRAP-05-2), http://el.erdc.usace.army.mil/wrap/pdf/tnwrap05-2.pdf U.S. Army Engineer Research and Development Center, Vicksburg, MS.
- U.S. Army Corps of Engineers. 2006. Minimum monitoring requirements for compensatory mitigation projects involving the creation, restoration, and/or enhancement of aquatic resources. Regulatory Guidance Letter No. 06-03.

Table 1
Example Cross-reference between Mitigation Plan and New England District, U. S. Army Corps of Engineers *Mitigation Plan Checklist* (2004).

Check-	Description	Relevant	Page						
list Item		Section	Number						
A. General Information									
1.	One complete package								
2.a	Locus map	Figure 1							
2.b	Aerial photo	Figure 2							
2.c	Lat/Long	Figure 1							
2.d	HUC	Section A	p.1						
B. Impac	ct Area(s)								
1.	Wetland acreage	Section A	p.2, Table 1						
2.	Wetland classes	Section A	p.3, Table 1						
3.	Streams	Section A	p. 3, Table 1						
4.	Wetland and stream functions and values	Section A	p.3, Table 1						
5.	Type and purpose of work	Section A	p. 3						
6.	Watershed plans	Section A	p. 4						
C. Mitiga	ation Area(s)								
1.a	Mitigation alternatives	Section B							
1.b	Existing wildlife use	Section C	p.2						
1.c	Existing soil	Section C	p.3						
1.d	Existing vegetation	Section C	p. 7						
1.e	Surrounding land use	Section C	p.9						
1.f	USFWS Clearance Letter	Section C	p.12						
1.g	SHPO Clearance Letter	Section C	p. 13						
2.a	Wetland acreages and mitigation types at each site	Section D	p. 1, Table 2						
2.b	Wetland classes at each site	Section D	p. 2, Table 2						
2.c	Functions and values proposed at each site	Section D	p. 2, Table 2						
2.d	Stream mitigation	Section D	p.3						
2.e	Reference site(s)	Section D	p. 4						
2.f	Design Constraints	Section E	p.1						
2.g	Construction oversight	Section E	p. 2						
2.h	Project construction timing	Section E	p. 3						
2.i	Responsible parties	Section E	p. 5						
2.j									
2.k	FAA Issues	Section E	p.6						
D. Hydro	ology								
1.	Adequate hydrology	Section G	p. 8, Tables						
			3, 4						

1.a	Typical year water budget	Section G	Figure 1
1.b	Wet year water budget	Section G	Figure 2
1.c	Dry year water budget	Section G	Figure 3
2.	Water source(s)	Section G	
3.	If vernal pool, adequate hydrology	Section G	p. 8
		Section G	p. 9, 23
	ading Plan	1. 4	D: 0.5
1.a	Plan View – existing and proposed contours	Appendix A	Figures 2-5
1.b	Plan View – microtopography	Appendix A	Figures 2-5
1.c	Plan View – scale	Appendix A	
1.d	Plan View – legible	Appendix A	
1.e	Plan View – bar scale	Appendix A	
2.	Representative cross-sections	Appendix A	Figures 7-9
3.	Other grading comments (if any)	N/A	
F. Top	psoil		
1.	Proposed source	Section H	p. 1
2.	Depth	Section H	p. 5,
			Figures 7-9
3.	Organic content	Section H	p. 6
G. Pla	nting Plan		
1.	Scientific names	Appendix A	Figures 2-5
2.	Native materials, no invasive species	Section H	pp. 8, 11
	plantings		
3.	Community types	Section H	p. 8
4.	Location on plans	Appendix A	Figures 2-5
5.	Plantings for community type	Section H	p. 8
6.	Woody stock density	Appendix A	Figures 2-5
7.	Herbaceous stock density	N/A	
8.	Seed mix composition	Section H	p. 10
9.	Cross-sections	Appendix A	Figures 7-9
10.	Relocation text	Section H	p. 12
11.	Other	N/A	
H. Coa	arse Woody Debris and Other Features	•	
	Is proposed	Appendix A	Figure 2-5
I. Eros	sion Controls	, **	
	Deadline for removal	Section H	p. 7
J. Inv	asive and Noxious Species	_1	1
1.	Risk	Section I	p. 1
2.	Constraints	Section I	p. 1
3.	Control plan	Section I	p. 2
	F-Road Vehicle Use		
1.	Usage in vicinity	Section I	p. 4
2.	Control plan	N/A	P. '
	servation	11/11	
D. FIE	201 A M CI A II		I

1.	Adequate buffers	Section J	p. 1				
2.	Internal wetlands protected	Section J	Figure 10				
3.	Preservation language	Section J	p. 2				
4.	Preservation site plans	Section J	Figure 11				
5.	Legal instrument(s)	Section J	p. 5				
6.	Acceptance by receiving agency	Section J	p. 5				
M. Moni	M. Monitoring Plan						
	Appropriate language Section K						
N. Asses	N. Assessment Plan						
	Appropriate language	Section L					
O. Contingency							
P. Long-							
Q. Other							

Table 2
Sample Summary of Proposed Wetland Mitigation

MITIGATION SITE	TYPE OF MITIGATION	SIZE
1	Wetland Enhancement (E), Restoration (R), and Creation (C)	E = 15,600 s.f. R = 49,560 s.f. C = 15,900 s.f.
2	Wetland Creation	42,100 s.f.
3	Wetland Preservation (note: sites 1 and 2 to be preserved as well)	13.5 acres
3	Upland Preservation	6.3 acres

Table 3
Sample Wetland Impact Area Function-Value Summary

Wetla		Wetland	WETLAND FUNCTIONS AND VALUES												
nd Impac t Area #	Area (s.f.)	Type (Cowardin)	G W R / D	F F A	S & T R	N R & T	P E	\$ & \$	F & S H	W L H	Т & Е	R E C	E D / S	U / H	V Q / A
1	31,350	PFO1/ PSS1B	Х	Х						Р					Х
2	14,190	PEM1/ PSS1B	Х	Р		Х			Х	Х					
3	23,600	PFO1	Х							Р		Х			
4	49,010	PSS1B	X	Х		X				Р					X
5	2,350	PEM1		Х	Х	Х		Р		Х					

Table 4 Invasive and other Unacceptable Plant Species¹⁰

a. Herbs:

Aegopodium podagraria

Aira caryophyllea Alliaria petiolata Allium vineale

Ampelopsis brevipedunculata Anthoxanthum odoratum

Anthriscus sylvestris

Arctium minus

Asparagus officinalis Barbarea vulgaris Bromus tectorum

Butomus umbellatus Cabomba caroliniana Callitriche stagnalis

Calystegia sepium Cardamine impatiens Cardamine pratensis

Carex kobomugi

Centaurea biebersteinii

Chelidonium majus Cirsium arvense Cirsium palustre Commelina communis

Coronilla varia Cyperus esculentus Dactylis glomerata Datura stramonium Echinochloa crusgalli

Egeria densa

Eichhornia crassipes

Eleusine indica Elsholtzia ciliata Elytrigia repens Epilobium hirsutum Euphorbia cyparissias

Euphorbia esula Festuca filiformia Festuca ovina Goutweed or Bishop's weed

Silver hairgrass Garlic mustard Field garlic Porcelain berry Sweet vernal grass

Chervil

Common burdock

Asparagus Yellow rocket

Drooping brome-grass

Flowering rush

Fanwort

Water-starwort
Japanese bindweed
Bushy rock-cress
Cuckoo-flower
Japanese sedge
Spotted knapweed

Celandine
Canada-thistle
Marsh thistle
Asiatic day-flower
Crown vetch

Yellow nutsedge
Orchard-grass
Jimsonweed
Barnyard grass
Giant waterweed
Water hyacinth
Goosegrass
Elsholtzia
Quack-grass
Hairy willow-herb
Cypress spurge
Leafy spurge
Hair fescue
Sheep fescue

NEW ENGLAND DISTRICT REGULATORY DIVISION

¹⁰ Scientific names are those used in Gleason, Henry and A. Cronquist, 1991. *Manual of Vascular Plants of*Northeastern United States and Adjacent Canada: Second Edition, The New York Botanical Garden: New York.

5/25/2004 DRAFT

U.S. ARMY CORPS OF ENGINEERS

NEW ENGLAND DISTRICT

Froelichia gracilis Geranium nepalense (G. sibericum)

Geranium thunbergii Glaucium flavum Glechoma hederacea Glyceria maxima

Hemerocallis fulva

Heracleum mantegazzianum Hesperis matronalis

Hydrilla verticillata

Hydrocharis morsus-ranae

Hylotelephium telephium (Sedum telephium) Live-forever or Orpine

Hypericum perforatum St. John's wort

Impatiens glandulifera Ornamental jewelweed

Iris pseudacorus Yellow iris

Kochia scopariaSummer cypressLamium spp. (all)Dead nettleLepidium latifoliumTall pepperwortLotus corniculatusBirdsfoot trefoil

Lysimachia nummularia Moneywort Lysimachia vulgaris Garden loosestrife

Lythrum salicaria Purple loosestrife

Malva neglecta Cheeses or common malva

Marsilea quadrifolia Water shamrock or Eu. water clover

Slender snake cotton

Nepalese crane's-bill

Thunberg's geranium

Sea- or horned poppy

Gill-over-the-ground

Sweet reedgrass

Giant hogweed

Dame's rocket

European frog-bit

Tiger-lily

Hvdrilla

Mentha arvensis Field-mint

Microstegium vimineum Japanese stilt-grass

Miscanthus sinensis Eulalia

Myosotis scorpioidesTrue forget-me-notMyosoton aquaticumGiant chickweedMyriophyllum aquaticumParrot feather

Myriophyllum heterophyllumVariable water-milfoilMyriophyllum spicatumEurasian water-milfoil

Najas minor Lesser naiad

Nymphoides peltata Yellow floating heart
Ornithogalum umbellatum Star of Bethlehem

Pastinaca sativa Wild parsnip

Phalaris arundinacea Reed canary-grass
Phragmites australis Reed grass, Phragmites

Poa compressaCanada bluegrassPoa pratensisKentucky bluegrassPoa trivialisRough bluegrassPolygonum aubertiiSilver lace-vine

Polygonum cespitosumCespitose knotweedPolygonum cuspidatumJapanese knotweedPolygonum perfoliatumMile-a-minute vine

Polygonum persicariaLady's thumbPolygonum sachalinenseGiant knotweedPotamogeton crispusCurly pondweedPuccinellia maritimaSeaside alkali-grass

Pueraria montana Kudzu

Ranunculus ficariaLesser celandineRanunculus repensCreeping buttercupRorippa microphyllaOne-row yellow cress

Rorippa nasturtium-aquaticum Watercress

Rorippa sylvestris Creeping yellow cress

Rumex acetosellaSheep-sorrelRumex obtusifoliusBitter dockSalvinia molestaSalvinia

Senecio jacobaea Tansy ragwort

Setaria pumila (S.lutescens, S. glauca) Yellow foxtail or y. bristlegrass

Silphium perfoliatum Cup plant

Solanum dulcamara Bittersweet nightshade Stellaria graminea Common stitchwort

Tanacetum vulgareTansyThymus pulegioidesWild thymeTrapa natansWater-chestnut

Tussilago farfara Coltsfoot

Typha latifolia¹¹ Common or Broad-leaved cattail

Typha angustifolia4Narrow-leaved cattailValeriana officinalisGarden heliotropeVerbascum thapsusCommon mulleinVeronica beccabungaEuropean speedwellVincetoxicum rossicum (V. nigrum)Black swallow-wortXanthium strumariumCommon cocklebur

b. Woody Plants:

Acer ginnalaAmur mapleAcer platanoidesNorway mapleAcer pseudoplatanusSycamore maple

Actinidia arguta Kiwi vine

Ailanthus altissima
Alnus glutinosa
Berberis thunbergii
Berberis vulgaris
Catalpa speciosa

Tree-of-heaven
European alder
Japanese barberry
Common barberry
Western catalpa

¹¹ *Typha* spp. are native species which provide good water quality renovation and other functions/values. However, they are aggressive colonizers which, given the opportunity, will preclude establishment of other native species. They are included in this list as species not to be planted, not because they are undesirable in an established wetland, but to provide opportunities for other species to become established. It is likely they will eventually move in without human assistance.

Celastrus orbiculatus Cynanchum louiseae Cytisis scoparius Elaeagnus angustifolia Elaeagnus umbellata

Euonymus alata Euonymus fortunei Humulus japonicus

Hypericum prolificum Liqustrum obtusifolium

Liqustrum vulgare Lonicera japonica Lonicera maackii Lonicera morrowii Lonicera tartarica Lonicera x bella *Lonicera xylosteum*

Morus alba

Paulownia tomentosa Phellodendron japonicum

Populus alba

Rhamnus cathartica Rhamnus frangula Ribes sativum

Robinia pseudoacacia

Rosa multiflora Rosa rugosa

Rubus phoenicolasius

Salix purpurea¹² Sorbus aucuparia Taxus cuspidata Ulmus pumila

Wisteria floribunda

Oriental bittersweet Black swallow-wort

Scotch broom Russian olive Autumn olive

Winged euonymus Climbing euonymus

Japanese hops

Shrubby St. John's wort

Japanese privet

Common/hedge privet Japanese honeysuckle Amur honeysuckle Morrow's honeysuckle Tatarian honeysuckle

Morrow's X Tatarian honeysuckle

European fly-honeysuckle

White mulberry

Princess tree or empress tree

Corktree Silver poplar

Common buckthorn European buckthorn Garden red currant

Black locust Multiflora rose Rugosa rose Wineberry

Basket or purple-osier willow European mountain-ash

Japanese yew Siberian elm Wisteria

 $^{^{12}}$ This is not appropriate for use in wetland mitigation. In some circumstances it may be appropriate in stream bank stabilization.

ATTACHMENT 1

Project Overview Form

Corps Permit No.:
Mitigation Site Name(s):
Monitoring Report: of
Name and Contact Information for Permittee and Agent:
Name of Party Responsible for Conducting the Monitoring:
Date(s) of Inspection(s):
Project Summary:
[include purpose of approved project, acreage and type of aquatic resources impacted, and mitigation acreage and type of aquatic resources authorized to compensate for the aquatic impacts]
Location of and Directions to Mitigation Site:
Start and Completion Dates for Mitigation:
Performance Standards are/are not being met:
[describe how]
<u>Dates of Corrective or Maintenance Activities Conducted Since Last Report</u> :
Recommendations for Additional Remedial Actions:

ATTACHMENT 2

MITIGATION REPORT TRANSMITTAL AND SELF-CERTIFICATION

DEPARTMENT OF THE ARMY PERMIT NUMBER:	
PROJECT TITLE:	
PERMITTEE: MAILING ADDRESS:	
MAILING ADDRESS:	
TELEPHONE:	
AUTHORIZED AGENT:	
MAILING ADDRESS:	
TELEPHONE:	
ATTACHED MITIGATION REPORT	
TITLE:	
PREPARERS:	
DATE:	
CERTIFICATION OF COMPLIANCE: I certify that the at	
discloses that the mitigation required by the Department of t compliance with the terms and conditions of that permit.	he Army Permit [is] [is not] in full
compliance with the terms and conditions of that permit.	
CORRECTIVE ACTION: A need for corrective action [is]	[is not] identified in the attached
report.	
CONSULTATION: I [do] [do not] request consultation with	th the Corps of Engineers to discuss
a corrective strategy or permit modification.	
CERTIFIED:	
(Signature of permittee)	Date